Rossetta's Roofing Company
401 Lincoln Ave. San Jose, CA 95126

Roofing Estimate

Customer Name	Mr. & Mrs. Homeowner	February 13, 2012
Address	123 Main St.	
City/St/Zip	San Jose CA 95126	
Owner Name	Mr. & Mrs. Homeowner	
Job Address	123 Main St.	
Job City/St/Zip	San Jose CA 95126	

Type of Roofs	
Composition	
20 Year 3 Tab	$10,452.61
CertainTeed Landmark	$10,752.82
CertainTeed Landmark Pro	$11,344.14
CertainTeed Landmark Premium	$12,069.71
CertainTeed Landmark TL	$12,849.40
CertainTeed Presidential	$13,553.81
CertainTeed Presidential TL	$15,103.79
Tile	
Lightweight Tile	$16,965.65
Shake	
Medium Shake	$16,915.03
Heavy Shake	$18,429.32
Flat Roofing	
Torch Down	$0.00
Single Ply	$0.00
Type of Gutters	
Gutters	
Aluminum Pre Painted Seamless	$1,374.51
Bonderized	$1,633.62
Number of Downspouts	6

The above estimate by Rossetta's Roofing includes the following unless otherwise noted:
Obtain permit from local building department and applicable inspections at the time of installation
Number of roofs to be removed: Pitched: 2 Flat: 0
Sheeting material being installed: Plywood - 15/32" 3 Ply Plywood
The installation of 36" 30LB felt underlayment.
The installation of all new nosing over all gable edges, if necessary.
The installation of all new 26ga. galvanized valley, plumbing vents, and U.L. listed heater vent flashings.
All flashings to be painted with rust proof paint, to match the color of the roof as best as possible..
The installation of your new roof according to the city and manufacturers recommended procedures.
The installation of all new appropriate ridge shingles on all hips and ridges.
Clean up and haul away all resulting debris.
Estimates written by Rossetta's Roofing may be withdrawn if not accepted within thirty days.
Written contracts will be mailed upon request.
A conditional release will be provided with the final invoice if requested .
If you have any questions, please feel free to contact us at 408-294-4400.
Thank you for allowing Rossetta's Roofing to estimate your home.
Estimated by: Tony Cardoso